

ARCHITECT SPECIFICATIONS FOR PREFINISHED MATERIAL & CAROLINA COLORTONES.

GENERAL SPEC FOR ELEVATIONS:

- PREFINISHED SIDING AND TRIM BY CAROLINA COLORTONES

GENERAL SPECIFICATION FOR SUMMARY:

- EXTERIOR SIDING AND TRIM TO BE PREFINISHED PER MANUFACTURER'S RECOMMENDATIONS/WARRANTYS BY CAROLINA COLORTONES.

WOOD SIDING SPECIFICATIONS FOR ELEVATION:

- PREPRIMED/PREFINISHED "WOOD" SIDING AND TRIM

WOOD SIDING SPECIFICATIONS FOR SUMMARY:

- "WOOD" SIDING AND TRIM MUST BE ACCLIMATED AND DRIED TO APPROPRIATE MOISTURE CONTENT BEFORE FINISHING. "WOOD" TO BE BACKPRIMED OR PREFINISHED ON ALL SIX SIDES BY CAROLINA COLORTONES PER WRCLA & NELMA RECOMMENDATIONS.

CEMENT OR COMPOSITE SPECIFICATIONS FOR ELEVATIONS:

- FACTORY PRIMED/FINISHED CEMENT/COMPOSITE SIDING AND/OR TRIM.

CEMENT OR COMPOSITE SPECIFICATIONS FOR SUMMARY:

- CEMENT/COMPOSITE SIDING & TRIM TO BE DRY, CLEAN AND WARM BEFORE FINISHING. MATERIAL TO BE FACTORY PRIMED TO COLOR OR PREFINISHED BY CAROLINA COLORTONES TO ACCOMIDATE ALL MANUFACTURER'S GUIDELINES AND RECOMMENDATIONS.

INTERIOR WOOD SPECIFICATIONS FOR SUMMARY:

- INTERIOR T&G/TRIM TO BE PREPRIMED ON ALL SIX SIDES AND SANDED BY CAROLINA COLORTONES PREVIOUS TO INSTALLATION.
- INTERIOR T&G/TRIM TO BE STAINED ON ALL SIX SIDES, SANDED AND TOP COATED WITH POLYURATHANE (OIL/WATER)/DURATHANE PREVIOUS TO INSTALLATION.

Specifications available as a Word document in the Download section of www.carolinacolortones.com.